

XNG/TGT Electrical/Controls Devices:

- 120VAC Power Outlets 120V/24V Power Supply 120V and 24V Battery UPS
- 120V Panel Heater
- IDEC PLC
- Red Lion HMI

- XNG Supplied Cisco Meraki Router w/ LAN or Wireless Internet Supply
 Control Panel (NEMA 4X)
 MVD Modbus Direct Connect Device (For Micromotion CNG050 Flow Meter)
- 8-Port Network Switch

SYSTEM PARAMETERS:

MAOP = 4,500 PSIG MOP = 4,000 PSIG MIN PRESSURE = 500 PSIG FLOW RATE = 10 - 150 MSCFH TEMPERATURE = (-40F) - 140F

XNG/TGT: CUSTOM DISPENSER P&ID



REVISION HISTORY			
REV	DATE	DRAWN	DESCRIPTION
0	12/20/2024	BB	ISSUED FOR REVIEW